



- 3/4-1-1/2" (19-38mm) ADHERED MASONRY VENEER
- MORTAR SETTING BED
- 1/2-3/4" (13-19mm) MORTAR SCRATCH COAT W/
 - Min. 1/4" (6mm) FURRED, FULLY EMBEDDED METAL LATH (EXPANDED, RIBBED, WOVEN, WELDED)
 - CORROSION RESISTANT METAL FASTENERS ATTACHED TO ICF WEBS AT 10x6" (254x152mm) o.c. (#8 COARSE THREAD 2-1/2" (64mm) SCREW WITH 1-1/4" (32mm) METAL WASHER)
- 3/8" (10mm) DIMPLED DRAINAGE MEMBRANE
- WEATHER RESISTIVE BARRIER (WRB)
- 8" (203mm) R22 ICF
- 1/2" (13mm) GYPSUM BOARD

WET SET DOWELS TO MARCH VERTICAL REINFORCEMENT BETWEEN POURS AS REQUIRED

CONCRETE SLAB REINFORCEMENT AS PER STRUCTURAL DESIGN

MORTAR JOINT (WHERE USED)

HORIZONTAL AND VERTICAL REINFORCEMENT AS PER STRUCTURAL DESIGN

8" R22 ICF WITH DRAINED ADHERED MASONRY VENEER

